

...about 1 year in operation – everything is fine...

Thanks to our great team and to the guys from MARTI for their support!

Objekt: Tunnel-Hauptentwässerung - SEMMERING BASISTUNNEL SBT 3.1

Für das Baulos 3.1 am Semmering Basistunnel, hat Häny Austria GmbH mit Sitz in Söding-St. Johann / Österreich, die maschinelle und elektrische Ausrüstung für die Tunnel-Hauptentwässerung geliefert.

Die Hauptpumpen am Schachtfuß fördern das gesamte anfallende Tunnelwasser über den 100m tiefen Schacht bis zur Gewässerschutzanlage Obertage.

Site: Main drainage - Semmering Base Tunnel SBT 3.1 (Austria)

Häny Austria GmbH, located in Söding-St. Johann, Austria, has delivered and put into operation the main drainage pumping station for the contract section 3.1 in the Semmering Base Tunnel.

The central pumping station near the bottom of the 100m deep shaft lifts the full expected volume of water to the watercourse protection facility on the base level.

Lieferumfang/ Scope of delivery:

4 customized pump units (pump, Motor, coupling, base frame) each with 250kW

2 collection tanks each with 30m³ volume

Piping installation

Base frame for tanks and pumps

Complete electrotechnical equipment







